SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAMBASIVA REDDY	
				Rate in Words	Rate in Figures
119	441.00	Providing and fixing of Aluminium composite panel of approved makeSqm 4,943.00and colour for wall cladding for straight Brick/Rcc/stone walls &coloumns/beams with necessary aluminium frame works at required level made out of 50x25x3mm C section or equalent. The panel shouldconsist of 2.5 mm thermoplastic core of antitoxic LDPE sandwichedbetween 0.25 skins thickaluminium sheet making a total panel thicknessof 3mm. The surfaces will be finished with PVDF based coating ontopsides and service coating on reverse sides would be in polyester paint. The system shall be fixed using GI brackets, aluminium L cleatsand stainless steel bolts and nuts complete with spring washer and capnuts and all other necessary accessories, sealing shall be done using weather sealant necessary rods etc., complete and as per directions of Engineer in charge of the work (First Floor) ---- All terms and condition are as per Tender Document	Sqm	5800.00	Rupees Five Thousand Eight Hundred Only
120	92.04	Providing, fabricating and fixing of stick type structural glazing using Alluminium Extrusions of 63.5 mm x 58.00 mmx 2.25 mm of 1.73 kgs/ mtr for vertical and Horizontal members and 63.5 mm x 38.1 x 1.33 mm of 0.759 kg/Mtr, as outer frame with Electro Anodized Paint coated block finishing, using 6mm thick imported glass reflective hard coatedocean blue raw glass with all necessary accesories like ultra glass Silicon sealant of Space tape, Masking tape, Galvanized Anchaor bolt, machine screws, 6mm thick M.S. angle 50mm x 150mm x 6mm M.S. Galvanized L Brackets, structural sealent setting clocks, fasteners, wall connection etc., complete and as per directions of Engineer in charge of the work (Ground Floor) ---- All terms and condition are as per Tender Document	Sqm	5800.00	Rupees Five Thousand Eight Hundred Only
121	540.00	Providing, fabricating and fixing of stick type structural glazing using Alluminium Extrusions of 63.5 mm x 58.00 mmx 2.25 mm of 1.73 kgs/ mtr for vertical and Horizontal members and 63.5 mm x 38.1 x 1.33 mm of 0.759 kg/Mtr, as outer frame with Electro Anodized Paint coated block finishing, using 6mm thick imported glass reflective hard coatedocean blue raw glass with all necessary accesories like ultra glass Silicon sealant of Space tape, Masking tape, Galvanized Anchaor bolt, machine screws, 6mm thick M.S. angle 50mm x 150mm x 6mm M.S. Galvanized L Brackets, structural sealent setting clocks, fasteners, wall connection etc., complete. ---- All terms and condition are as per Tender Document	Sqm	6346.00	Rupees Six Thousand Three Hundred Forty Six Only
122	88.56	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications ---- All terms and condition are as per Tender Document	Sqm	100.00	Rupees One Hundred Only
123	812.58	Conveying the excavated earth, debries etc., with all lead and lifts including loading and unloading charges etc., complete as per the direction of the Engineer-in-charge. ---- All terms and condition are as per Tender Document	Cum	100.00	Rupees One Hundred Only

Contractor

Executive Engineer,
Project Division,Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAME REDDY	
				Rate in Words	Rate in Figure
124	11.88	Providing and fixing M.S. Gate as per Chief Architect Drawing,using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specification. ---- All terms and condition are as per Tender Document	Sqm	3300.00	Rupees Three Thousand Three Hundred Only
125	4.00	Providing 20mm square M.S footrest and fixing in manhole with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications. ---- All terms and condition are as per Tender Document	Nos	280.00	Rupees Two Hundred Eighty Only
126	1.00	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its quality & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Each BW	2000.00	Rupees Two Thousand Only
127	50.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars and cap etc.,) ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 0 to 50 m ---- All terms and condition are as per Tender Document	Rmtr	315.00	Rupees Three Hundred Fifteen Only
128	50.00	50 to 100 m ---- All terms and condition are as per Tender Document	Rmtr	412.00	Rupees Four Hundred Twelve Only
129	50.00	100 to 150 m ---- All terms and condition are as per Tender Document	Rmtr	458.00	Rupees Four Hundred Fifty Eight Only
130	50.00	150 to 200 m ---- All terms and condition are as per Tender Document	Rmtr	484.00	Rupees Four Hundred Eighty Four Only
131	50.00	200 to 250 m ---- All terms and condition are as per Tender Document	Rmtr	560.00	Rupees Five Hundred Sixty Only
132	50.00	250 to 300 m ---- All terms and condition are as per Tender Document	Rmtr	600.00	Rupees Six Hundred Only

Contractor

Executive Engineer,
Project Division,Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAMBASIVA REDDY	
				Rate in Words	Rate in Figures
133	70.00	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes) ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Rmtr	1400.00	Rupees One Thousand Four Hundred Only
134	18.00	Providing 250mm dia PVC Pipe 6kg/cm as per specification and direction of the Engineer in Charge of the work ---- All terms and condition are as per Tender Document	Rmtr	1100.00	Rupees One Thousand One Hundred Only
135	1.00	Providing and fixing 175mm Borewell Cap with clamp Set H/D,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	No.	100.00	Rupees One Hundred Only
136	1.00	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 10.00 HP 20 stage.with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 12.50 HP 20 stage ---- All terms and condition are as per Tender Document	No	60400.00	Rupees Sixty Thousand Four Hundred Only
137	260.00	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour, charges HOM of equipments etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Rmtr	431.00	Rupees Four Hundred Thirty One Only
138	540.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Mtr	128.00	Rupees One Hundred Twenty Eight Only
139	130.00	Labour charges for erection as new /repaired submercible pumpset allong with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset shoud be handed over to department including transportation (Each lenth =6.00)etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	M	88.00	Rupees Eighty Eight Only
140	1.00	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	No.	302.00	Rupees Three Hundred Two Only
141	30.00	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class.with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Mtr	141.00	Rupees One Hundred Forty One Only

Contractor

Executive Engineer,
Project Division,Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAI REDDY	
				Rate in Words	Rate in Figu
142	30.00	Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR 1999-2000, with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Mtr	11.00	Rupees Eleven Only
143	25.00	Digging or trenching of 0.6 m x 0.5 m wide refilling the trench to the required ground level and consolidating etc., complete as per Civil SR KSRB 1-2 P-7 with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Mtr	90.00	Rupees Ninety Only
144	4.00	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Mtr	450.00	Rupees Four Hundred Fifty Only
145	1.00	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc.,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	No.	350.00	Rupees Three Hundred Fifty Only
146	1.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia, (PWD Electrical SR-1999-2000, with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	No	3500.00	Rupees Three Thousand Five Hundred Only
147	6.00	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc.,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	No.	195.00	Rupees One Hundred Ninety Five Only
148	1.00	Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	No	1700.00	Rupees One Thousand Seven Hundred Only
149	1.00	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete.with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	No	450.00	Rupees Four Hundred Fifty Only
150	4.00	SSupplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	No	110.00	Rupees One Hundred Ten Only
151	1.00	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materiasl wiring complete as requireds 5 to 30 amps triple pole with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	No	1600.00	Rupees One Thousand Six Hundred Only

Contractor

Executive Engineer,
Project Division,Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAMBASIVA REDDY	
				Rate in Words	Rate in Figures
152	23400.00	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Sq.Cm	0.33	Rupees And Paise Thirty Three Only
153	1.00	Supplying fully automatic store detta starer unit push button type with suitable wires three contractors one adjustable termal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts 3pase and wired offter fixing to the wooden board for motor upto 12.50 HP with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Each	7000.00	Rupees Seven Thousand Only
154	112.50	Earthwork excavation for pipeline foundation including deporiting or bank up to a depth of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Cum	190.00	Rupees One Hundred Ninety Only
155	250.00	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 75mm Dia 6 KSC ---- All terms and condition are as per Tender Document	Rmtr	160.00	Rupees One Hundred Sixty Only
156	112.50	Refilling the bumont and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrswith all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Cum	62.00	Rupees Sixty Two Only
157	3.00	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specification with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work ---- All terms and condition are as per Tender Document	Each	2300.00	Rupees Two Thousand Three Hundred Only
158	2350.00	Concealed Conduit System Supplying heavy gauge PVC conduit pipe .....mm dia .....mm thick confirming to IS 2509 with suitable size bends, metal/PVC junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary19/20mm dia 2mm thick(including audio system) ---- All terms and condition are as per Tender Document	Mtr	45.00	Rupees Forty Five Only
159	950.00	25mm dia 2mm thick ---- All terms and condition are as per Tender Document	Mtr	60.00	Rupees Sixty Only
160	200.00	32mm dia 2.5mm thick ---- All terms and condition are as per Tender Document	Mtr	90.00	Rupees Ninety Only
161	372.00	Extra for Groove cutting in brick wall/CC floor to the suitable depth for concealing of Conduit/GI pipe and plastering, finishing upto wall surface complete. upto 50mm conduit in brick wall ---- All terms and condition are as per Tender Document	Mtr	22.00	Rupees Twenty Two Only

Contractor

Executive Engineer,
Project Division,Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAI REDDY	
				Rate in Words	Rate in Figu
162	20.00	upto 50mm conduit CC floor ---- All terms and condition are as per Tender Document	Mtr	40.00	Rupees Forty On
163	50.00	Supplying and fixing of PVC casing and capping on the wall or ceiling using necessary materials like bends, screws at an interval of 300mm .... etc. as required. 25mm ---- All terms and condition are as per Tender Document	Mtr	30.00	Rupees Thirty Only
164	50.00	32mm ---- All terms and condition are as per Tender Document	Mtr	40.00	Rupees Forty Only
165	200.00	Supplying PVC/GI flexible conduit pipe...mm dia fixing on surface over inverted tapered wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and on either end of the pipe terminated completely 25mm ---- All terms and condition are as per Tender Document	Mtr	32.00	Rupees Thirty Two Only
166	23.00	Supplying And Fixing Metal Fan Box with Round Hook. ---- All terms and condition are as per Tender Document	No	95.00	Rupees Ninety Five Only
167	5.00	Point wiring using Copper wire without switch. Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2X1.5Sq.mm Cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block complete for each outlet. GROUP A Short point upto 3Mtr from tapping point to out let via switch box ---- All terms and condition are as per Tender Document	Point	150.00	Rupees One Hundred Fifty Only
168	25.00	Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch box ---- All terms and condition are as per Tender Document	Point	230.00	Rupees Two Hundred Thirty Only
169	57.00	Long point above 6Mtr upto 10Mtr from tapping point to out let via switch box ---- All terms and condition are as per Tender Document	Point	350.00	Rupees Three Hundred Fifty Only
170	5.00	Two outlet in a row, above 3Mtr upto 6Mtr from tapping point to out let via switches ---- All terms and condition are as per Tender Document	Point	450.00	Rupees Four Hundred Fifty Only
171	18.00	Three outlet in a row, above 6Mts upto 10Mtr from tapping point to out let via switches box ---- All terms and condition are as per Tender Document	Point	600.00	Rupees Six Hundred Only
172	5750.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A.1.5 sqmm ---- All terms and condition are as per Tender Document	Mtr.	19.00	Rupees Nineteen Only
173	3200.00	2.5 sqmm ---- All terms and condition are as per Tender Document	Mtr.	30.00	Rupees Thirty Only
174	650.00	4 sqmm ---- All terms and condition are as per Tender Document	Mtr.	43.00	Rupees Forty Three Only
175	150.00	6 sqmm ---- All terms and condition are as per Tender Document	Mtr.	65.00	Rupees Sixty Five Only
176	450.00	10 sqmm ---- All terms and condition are as per Tender Document	Mtr.	110.00	Rupees One Hundred Ten Only
177	17.00	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall 1-3Way -- All terms and condition are as per Tender Document	Each	92.00	Rupees Ninety Two Only
178	9.00	6Way ---- All terms and condition are as per Tender Document	Each	135.00	Rupees One Hundred Thirty Five Only
179	26.00	8Way ---- All terms and condition are as per Tender Document	Each	150.00	Rupees One Hundred Fifty Only
180	9.00	10-12Way ---- All terms and condition are as per Tender Document	Each	160.00	Rupees One Hundred Sixty Only
181	17.00	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. 1 to 3 Module ---- All terms and condition are as per Tender Document	Each	110.00	Rupees One Hundred Ten Only
182	9.00	6 Module ---- All terms and condition are as per Tender Document	Each	180.00	Rupees One Hundred Eighty Only

Contractor

Executive Engineer,
Project Division, Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAMBASIVA REDDY	
				Rate in Words	Rate in Figures
183	26.00	8 Module ---- All terms and condition are as per Tender Document	Each	200.00	Rupees Two Hundred Only
184	9.00	12 Module ---- All terms and condition are as per Tender Document	Each	270.00	Rupees Two Hundred Seventy Only
185	210.00	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 GROUP A 6Amps one way. ---- All terms and condition are as per Tender Document	Each	65.00	Rupees Sixty Five Only
186	4.00	6Amps Two way. ---- All terms and condition are as per Tender Document	Each	90.00	Rupees Ninety Only
187	32.00	6Amps 3way socket. ---- All terms and condition are as per Tender Document	Each	97.00	Rupees Ninety Seven Only
188	23.00	Stepped Fan Regulator. ---- All terms and condition are as per Tender Document	Each	290.00	Rupees Two Hundred Ninety Only
189	10.00	16Amps one way switch ---- All terms and condition are as per Tender Document	Each	118.00	Rupees One Hundred Eighteen Only
190	10.00	6/16Amps universal socket ---- All terms and condition are as per Tender Document	Each	150.00	Rupees One Hundred Fifty Only
191	1.00	TV/Telephone socket ---- All terms and condition are as per Tender Document	Each	83.00	Rupees Eighty Three Only
192	1.00	RJ45/ I.O. outlet ---- All terms and condition are as per Tender Document	Each	205.00	Rupees Two Hundred Five Only
193	750.00	Supplying 50mm wooden plug, tapered from 50x50mm to 25x25mm and fixing by using binding wire before concreting a roof slab. ---- All terms and condition are as per Tender Document	No	7.00	Rupees Seven Only
194	12.00	Supplying and fixing cast Aluminum round or oblong type bulk head fitting with GI wire guard, glass cover with 15Watts 230V CFL lamp. ---- All terms and condition are as per Tender Document	Each	970.00	Rupees Nine Hundred Seventy Only
195	4.00	Supplying CFL mirror light fitting with 1x11W CFL lamp, choke, Perspex cover and completely wired for use on 230V 50Hz AC supply. ---- All terms and condition are as per Tender Document	Each	650.00	Rupees Six Hundred Fifty Only
196	225.00	LED Indoor Supplying of 2' feet - LED PVC Square Batten ..W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50Hz & Power factor >0.9 along with CE approved drivers. 5 years Warranty against any manufacturing defect working under standard electrical condition LED light fighting 4' - 28 watts ---- All terms and condition are as per Tender Document	Each	1800.00	Rupees One Thousand Eight Hundred Only
197	25.00	Supply of recess mounted rolling type LED square or round Down light 12 watts with 4/6W GU 10 LED Lamp Rib Fabricated from Die cast aluminum with white powder coated prewired to mains connector with suitable driver & having swiveling unit of aluminum die cast eye ball & LED Lamp position retained by circular wire spring. 5 years Warranty against any manufacturing defect working under standard electrical condition. ---- All terms and condition are as per Tender Document	No	1900.00	Rupees One Thousand Nine Hundred Only
198	40.00	Supply of LED Square Recessed Down lighter with 18W System Wattage. Housing shall be with powder coated pressure die cast aluminum alloy with corrosion resistant polyester powder coat & with extended heat sink. Diffuser/cover made of Lexan plastic material. Rated life shall be L70 @ 50000 Hrs. which shall has inbuilt electrical protection like over/under voltage, short circuit, overload, open circuit & miswiring. Driver is on constant current driver output driver @ 0.06A with PF > 0.9 with line voltage @ 220-240V @ 50/60Hz, driver efficiency > 85% & THD<15%. LED Efficiency > 130 lm/W at 1W & Fixture Efficiency >75lm/w with CRI > 75 with injection moulded Polycarbonate lens. 5 years Warranty against any manufacturing defect working under standard electrical condition. ---- All terms and condition are as per Tender Document	No	5000.00	Rupees Five Thousand Only
199	80.00	60W highbay LED linear type light fixture make-crompton ,model - LHBL60CDL ---- All terms and condition are as per Tender Document	No	8000.00	Rupees Eight Thousand Only

Contractor

Executive Engineer
Project Division,Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAMB... REDDY	
				Rate in Words	Rate in Figure...
200	6.00	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.100Amps ---- All terms and condition are as per Tender Document	Each	400.00	Rupees Four Hundred... Only
201	1.00	Supplying of on load change over switches 4 poles, AC-23A Duty, 415V, 50Hz, AC Supply. 100-125Amps ---- All terms and condition are as per Tender Document	Each	6800.00	Rupees Six Thousand Eight Hundred Only
202	2.00	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) FOUR POLE 125-160Amps 25kA. ---- All terms and condition are as per Tender Document	Each	7500.00	Rupees Seven Thousand Five Hundred Only
203	3.00	Supplying and fixing of Shunt trip suitable for MCCB.CBCT. ---- All terms and condition are as per Tender Document	Each	1500.00	Rupees One Thousand Five Hundred Only
204	85.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.5-32Amps SP ---- All terms and condition are as per Tender Document	Each	420.00	Rupees Four Hundred Twenty Only
205	6.00	40-63Amps DP ---- All terms and condition are as per Tender Document	Each	1100.00	Rupees One Thousand One Hundred Only
206	6.00	40-63Amps TPN ---- All terms and condition are as per Tender Document	Each	1100.00	Rupees One Thousand One Hundred Only
207	6.00	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.II - Double Door 12Way SP &N ---- All terms and condition are as per Tender Document	Each	1700.00	Rupees One Thousand Seven Hundred Only
208	2.00	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.III - Double Door 4Way TP &N ---- All terms and condition are as per Tender Document	Each	2400.00	Rupees Two Thousand Four Hundred Only
209	6.00	Supplying, fixing and wiring Earth Leakage Miniature Circuit Breaker [ELMCB] 240/450V up to 300mA sensitivity on existing wood/panel board.32-40 Amps 2 pole ---- All terms and condition are as per Tender Document	Each	2700.00	Rupees Two Thousand Seven Hundred Only
210	1.00	32-40 Amps 4 pole ---- All terms and condition are as per Tender Document	Each	2950.00	Rupees Two Thousand Nine Hundred Fifty Only
211	1.00	63 Amps 4 pole ---- All terms and condition are as per Tender Document	Each	3350.00	Rupees Three Thousand Three Hundred Fifty
212	1.00	Supplying, fixing and wiring earth leakage relay with core balanced current transformer suitable for single phase 50 Hz AC with latest microcontroller based, digital readout of percentage leakage current, programmable delay/auto/manual reset facility suitable to mount on DIN rail/ flush mounting on panel board. ---- All terms and condition are as per Tender Document	Each	8000.00	Rupees Eight Thousand Only
213	1.00	Supplying, fixing and wiring 0 to 600Volts 96x96mm AC Voltmeter on existing panel/wood board. ---- All terms and condition are as per Tender Document	Each	390.00	Rupees Three Hundred Ninety Only
214	1.00	Supplying, fixing and wiring 0 to 100amps Direct Reading AC analog type Ammeter ---- All terms and condition are as per Tender Document	Each	452.00	Rupees Four Hundred Fifty Two Only
215	1.00	Supplying, fixing and wiring rotary selector switch suitable for Ammeter. ---- All terms and condition are as per Tender Document	Each	172.00	Rupees One Hundred Seventy Two Only
216	1.00	Supplying, fixing and wiring rotary selector switch suitable for Voltmeter. ---- All terms and condition are as per Tender Document	Each	150.00	Rupees One Hundred Fifty Only

Contractor

Executive Engineer,
Project Division,Yelahanka